

DELHI MILK SCHEME
GOVERNMENT OF INDIA
E- SHORT TENDER NOTICE

General Manager, Delhi Milk Scheme West Patel Nagar, New Delhi invites sealed items rate e- tender on behalf of The President of India for the under mentioned work/contract from approved and eligible contractors of CPWD, MCD, DDA, MES, PWD, NDMC etc. and those of appropriate approved list up to 31.05.2018

Name of work: - Repair / replacement of damaged mandana, Kota stone slabs and glazed Tiles in central dairy DMS West Patel Nagar New Delhi during 2018-19

Tender NO: - A/18403/01/DMS/2018-19

Estimated cost: - Rs.2, 88,146/-

Earnest Money: - Rs.5763/-

Time Allowed for execution of work: - 60 days

Tender form containing detailed schedule of work, terms and conditions can be downloaded from Central Public Procurement-Portal web site i.e. eprocure.gov.in/e-procure/app from **06.06.2018 to 20.06.2018 up to 2.30 PM**. Online tender documents must be accompanied with scanned copy of EMD as prescribed in tender document in favour of General Manager, Delhi Milk Scheme payable at Delhi of schedule bank. Original DD/Pay order/Bankers cheque for EMD may be submitted to this office well before opening of tender. Duly filled in e-tender / online offers shall be accepted up to 2.30 PM on **20.06.2018** and will be opened on **21.06.2018 at 2.30 P.M.** Manual tender shall not be accepted. Please also visit DADF Website i.e. dahd.nic.in

(Deepak Kumar Chaudhary)
General Manager



Name of work; - Repair/ Replacement of damaged mandana, Kota stone slabs and Glazed tiles in C.D. (DMS) during 2018-19

SCHEDULE OF WORK

S.NO.	Description of items	qty.	unit	rate	Amount(Rs.)
1.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 m lead.	150.00	sqm	-----	-----
2.	Providing and fixing 1 st quality ceramic glazed wall tiles conforming to IS: 15622(thickness to specified by the manufacturer) of approved make, in all colors, shades except burgundy, bottle green, black of any size as approved by engineer in charge, in skirting, risers of steps and dados .over 12 mm thick bed of cement mortar 1:3(1 cement: 3 coarse sand) and jointed with grey cement slurry @ 3.3. kg/sqm including pointing in white cement mixed with pigment of matching shade complete	125.00	sqm	-----	-----
3.	Providing and laying rectified glazed ceramic floor tiles of size 300X300 mm or more (thickness to be specified by the manufacturer) ,of 1 st quality conforming to IS: 15622 of approved make in colors white laid on 20 mm thick cement mortar 1:4(1 cement :4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete	20.00	sqm	-----	-----
4.	Kota stone slabs flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete with base of cement mortar 1:4(1 cement : 4 coarse sand) 25mm thick	75.00	sqm	-----	-----
5.	Providing and fixing mandana stone flooring with 25mm to 40 mm thick dressed mandana stone hand cut/ machine cut fixing thick 50 mm thick base of cement mortar 1:3(half part of cement, half part acid proof powder and 3 parts coarse sand including fixing the same in line and level with a specified groove of 12 mm all around including filling the joints with acid proof cement mortar with grinding, polishing etc. complete as directed by engineer in charge including removal of existing damaged				

R. B. B. B.

mandana stone up to dumping ground within 200 m lead and preparation of base etc. wherever required

75.00 sqm -----

6 Disposal of building rubbish / malba/ similar unserviceable, dismantled or waste material by mechanical means, including loading, transporting, unloading at municipal dumping ground or as approved by engineer in charge, beyond 50 m initial lead for all leads including all lifts involved

20.00 cum -----

6. Dismantling tiles work in floor and roofs laid in cement mortar including stacking material within 50 m lead for tile thickness up to 25mm

125.00 sqm -----

Total cost of work:- Rs. -----

CONDITIONS: - AS ENCLOSED



TERMS & CONDITIONS:-

- 1 Work will be executed as per specification 2009 and works manual of CPWD and as per direction of engineer in charge.
- 2 1%water and 1% electric charges (if electricity/water used) will be recovered from the gross amount of bill if the work is executed within DMS Premises.
- 3 Running payment will be made only after execution of 30 % work.
- 4 Rate so approved will be valid up to one year from the date of award of work
- 5 Further work can be awarded as and when required, for which a separate work order will be issued on the basis of approved rate, term and conditions after execution/completion of present/current contract/work
- 6 No any escalation will be considered in respect of hike in prices of labour and materials till the rate is valid/work completed
- 7 All the term and conditions clauses of the NIT and manual of CPWD & form 7/8 will be followed for contract / agreement as they stand or as may be altered from time to time
- 8 They shall employ the required technical staff and tools and plants as per term and conditions of contract
- 9 General Manager, Delhi Milk Scheme shall reserve right to reject any or all tenders without assigning any reasons and decision of GM(DMS) shall be final and binding
- 10 In case of any dispute the matter shall be referred to arbitrations of sole Arbitrator to be appointed by G.M. (DMS)
- 11 First class brick will be used instead of class designation 75 bricks/as approved by Engineer in charge.
- 12 No any extra payment will be made for any hidden item and work deviation limit 20% will be allowed only as mentioned in clause 12



